

## PROJECT SYNOPSIS

Project Name:	<b><i>Doha Convention Center &amp; Tower Project (2B/3B+G+110 Stories)</i></b>
Project Location:	<i>West Bay, Doha – Qatar</i>
Client / Main Contractor	<i>Qatari Diar</i>
Subcontract Amount:	<i>QR262,000,000/-</i>
Commencement:	<i>May 2007</i>
Completion:	<i>November 2008</i>
Scope Summary:	<ul style="list-style-type: none"><li>• <b><i>Design &amp; installation of shoring system, piling, excavation and dewatering for basement structure:</i></b></li><li>• <i>Diaphragm wall 800mm thick and 12m-17m deep, Length: 1,600m</i></li><li>• <i>Installation of removable ground anchors</i></li><li>• <i>900mm dia piles of 11m to 16m length : 2,030 no's</i></li><li>• <i>1,500mm dia piles of 25m to 34m length : 104 no's</i></li><li>• <i>Excavation volume: 1,172,109 cubic meter including disposal</i></li><li>• <i>Number of basements: 2 &amp; 3</i></li><li>• <i>Maximum depth of excavation in tower core area is 25m</i></li><li>• <i>Installation and maintenance of dewatering system.</i></li></ul>

